

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,179-20908-00-00

LEASE NAME Ballman

WELL NUMBER #1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 20 TWP. 9S RGE. 30 (E) or (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 8-17-88

Plugging Completed 8-26-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Kansas 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 17, 1988 (date)

by Gilbert Balthazor and Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORD | CASING RECORD

Formation	From	To	Size	Put In	Pulled out
			8-5/8"	258'	None
			5-1/2"	4292'	1,394.47'

RECEIVED
 STATE CORPORATION COMMISSION
 08-29-1988
 AUG 29 1988
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped sand to 4000' and 5 sacks cement. Shot casing at 2500, 2000, 1800, 1400'. Pulled 35 joints of 5-1/2" casing. Allied squeezed well with 5 sacks hulls and 350 sacks 60/40 pozmix cement with 6% added gel and 2% calcium chloride finished at 10:30 A.M. Max pressure was 300 psi and shutin 50 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 James W. Rockhold
 (Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1988

Jana M. Leatherman
 Notary Public

My Commission Expires: _____
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91