

15-193-20039-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Thomas County, Sec 3 Twp. 9S Rge. 31W (X) (W)
Location as "NE/CNW&SW" or footage from lines E/2 NE SW
Lease Owner Lewis M. Mull
Lease Name Johnson Well No. 1
Office Address 415 Page Court, 220 W. Douglas, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-13-72 19
Application for plugging filed 2-13-72 19
Application for plugging approved 2-13-72 19
Plugging commenced 2-13-72 19
Plugging completed 2-13-72 19
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud back to 1225 - plug & 110 sx. cement
Mud back to 310' - plug & 30 sx. cement
Mud back to 40 - plug & 10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1972
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1972
CONSERVATION DIVISION
Wichita, Kansas

02-25-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Kansas 67202 (Address)



Subscribed and Sworn to before me this 18th day of February, 1972
October 4, 1975
Juanita M. Green
Notary Public.

WELL LOG

15-193-20039-00-00

COMPANY Lewis M. Mull

SEC. 3 T. 9S R. 31W
LOC. E/2 NE SW

FARM Johnson NO. 1


RIG. NO. 1

TOTAL DEPTH 4315

COUNTY Thomas
KANSAS

COMM. 2-4-72

COMP. 2-13-72



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASING

20 10
15 8 5/8" @ 280' w/ 200 sx., 3% cc, 2% gel.
12 6
13 5

ELEVATION 2996 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay and Shale	175
Clay Shale	295
Shale	2321
Sand	2390
Shale and Red Bed	2604
Anhydrite	2636
Hard Sand	2700
Shale	3010
Shale w/ Lime Streaks	3300
Lime and Shale	3710
Lime	4315
Rotary Total Depth	4315

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1972
CONSERVATION DIVISION
Wichita, Kansas

02-25-1972

State of Kansas
County of Sedgwick } ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the Johnson #1 well.

Wilson Rains
WILSON RAINS

Subscribed and sworn to before me this 18th day of February 19 72

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green

My Commission Expires: October 4, 1975

