

15-193-20044-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Thomas County, Sec. 5, Twp. 9S Rge. (E) 31 (W)

Location as "NE/CNW&SW" or footage from lines NW NE  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name EVANS Well No. 1  
Office Address 801 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 28, 19 72  
Application for plugging filed (verbally) October 28, 19 72  
Application for plugging approved (verbally) October 28, 19 72  
Plugging commenced October 28, 19 72  
Plugging completed October 28, 19 72  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4325 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug set at 1677' w/110 cu. ft. cement  
2nd plug set at 280' w/30 cu. ft. cement  
3rd plug set at 40' w/10 sx. cement  
Job completed at 1:30 p.m. 10-28-72.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1972

CONSERVATION DIVISION  
Wichita, Kansas

11-01-1972

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Ks 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 1972

My commission expires February 10, 1975

Beverly Mann  
Beverly Mann Notary Public.

CONTRACTOR'S WELL LOG

15-193-20044-00-00

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	EVANS #1
LOCATION:	NW NE, Sec. 5-9S-31W Thomas County, Kansas
GEOLOGIST:	Orlin Phelps
SPUD DATE:	October 19, 1972
COMPLETION DATE:	October 28, 1972

0	216	Clay & Sand
216	260	Shale
260	335	Sand & Shale
335	845	Shale & Shells
845	1630	Shale
1630	2182	Shale, Clay & Sand
2182	2248	Shale
2248	2415	Sand
2415	2500	Shale
2500	2920	Shale & Anhydrite
2920	3093	Shale
3093	3537	Lime & Shale
3537	3690	Shale & Lime
3690	3930	Lime
3930	4050	Lime and Shale
4050	4325	Lime
	4325	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1972  
-01-1872  
CONSERVATION DIVISION  
Wichita, Kansas

Drilled 260' of 12½" surface hole. Set 8-5/8" sfs. csg. at 258' K.B. w/175 sx. Sunset cement. Cement circulated. Plug was down at 10:00 p.m. 10-19-72.  
Dry and Abandoned

ELECTRIC LOG TOPS

Anhydrite	2640 (+ 396)	<u>ELEVATION</u>
Heebner	4014 (- 978)	3036 K.B.
Toronto	4037 (-1001)	3034 D.F.
Lansing	4051 (-1015)	3028 G.L.
B/K.C.	4321 (-1285)	
ELTD	4328 (-1292)	

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK )

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the EVANS #1, NW NE, Section 5-9S-31W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
Jerry A. Langrehr  
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 30th day of October, 1972.

Beverly Mann  
Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975