

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-193-20280-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Thomas SEC. 24 TWP. 9S RGE. 31W E/W
 Location as in quarters or footage from lines:
660' S & 330' E of C

Locate Well
 correctly on above
 Section Platt.

Lease Owner Circle S Oil Company
 Lease Name Beckman Well No. 1
 Office Address HC39 Box 229, Hays, KS 67601
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 10-14-83
 Application for plugging filed 10-14-83
 Plugging commenced 10-14-83
 Plugging completed 10-14-83
 Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Shoemaker, Hays, KS
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8-5/8"	290'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

- 1st plug @ 2500' w/ 20 sx.
- 2nd plug @ 1705' w/100 sx.
- 3rd plug @ 340' w/ 40 sx.
- 4th plug @ 40' w/ 10 sx.
- 10 sx in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company


STATE OF Kansas COUNTY OF Sedgwick, ss.

David L. Murfin (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.


(Signature)

David L. Murfin - 250 N. Water, Suite 300
Wichita, KS 67202 (Address)

Subscribed and sworn to before me this 17th day of October, 19 83



Eleanor Hall
 Notary Public.



15-193-20280-00-00

WELL LOG

CIRCLE S OIL COMPANY
 COMPANY HC39 Box 229
 Hays, KS 67601
 FARM BECKMAN NO. 1
 RIG. NO. 16
 TOTAL DEPTH 4630
 COMM. 10-7-83 COMP. 10-14-83
 CONTRACTOR MURFIN DRILLING COMPANY
 250 N. Water, Suite 300
 Wichita, KS 67202
 CASING
 20 10
 15 8 -5/8" csg, set @ 290' w/220 sx Common,
 12 6 2% gel, 3% CC
 13 5

SEC. 24 T. 9S R. 31W
 LOC. 660' S & 330' E of C

COUNTY Thomas
 KANSAS

ELEVATION
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil & Sand & Clay	210'
Sand	220'
Shale	291'
Sand & Shale	2545'
Anhydrite	2579'
Shale	2955'
Shale & Lime (RTD)	4630'

State of Kansas
 County of Sedgwick } ss:
 I, David L. Murfin of the Murfin Drilling Company
 upon oath state that the above and foregoing is a true and correct copy of the log of the Beckman #1 well.
 Subscribed and sworn to before me this 17th day of October 19 83
 My Commission Expires: 4-25-87

David L. Murfin
 David L. Murfin

Eleanor Hall
 Eleanor Hall NOTARY PUBLIC

