

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-193-20,470-000

LEASE NAME Englehardt

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

4620 Ft. from E-Section Line

SEC. 30 TWP. 9S RGE. 31 ~~XXXX~~ (W)

COUNTY Thomas

LEASE OPERATOR Nye Exploration, Inc.

ADDRESS 803 N. Sheridan  
Suite 1200, Wichita, KS 67203

PHONE#(316) 946-0945 OPERATORS LICENSE NO. 3506

Date Well Completed 9-25-88

Character of Well good

Plugging Commenced 9-25-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-25-88

The plugging proposal was approved on 9-25-88 (date)

by State Plugger, Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Circulate heavy mud. 1st plug from 2650' to 2550' w/25 sx. 2nd plug from 1800' to 1400' w/100 sx and 15 sx of hulls. 3rd plug from 325' to 165' w/140 sx. 4th plug from 40' to surface w/10 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nye Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center  
Wichita, KS 67202

Rec'd 10-30-88

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1988

Jarvis M. Walker  
Notary Public

My Commission Expires: 10/24/90

