

STATE CORPORATION COMMISSION OF KANSAS  
OIL & GAS CONSERVATION DIVISION  
WELL COMPLETION FORM  
ACO-1 WELL HISTORY  
DESCRIPTION OF WELL AND LEASE

Operator: License # 4629

Name: Brito Oil Company, Inc.

Address 120 S. Market, Suite 300

Wichita, KS 67202

City/State/Zip \_\_\_\_\_

Purchaser: NCRA

Operator Contact Person: Raul F. Brito

Phone ( 316 ) 263-8787

Contractor: Name: White & Ellis Drilling, Inc.

License: 5420

Wellsite Geologist: Thomas Funk

Designate Type of Completion  
 New Well  Re-Entry  Workover

Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-Entry: old well info as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Comp. Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Deepening  Re-perf.  Conv. to Inj/SWD  
 Plug Back  PBTD  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (SWD or Inj?)  Docket No. \_\_\_\_\_

5.30.96 6.10.96 7.4.96  
Spud Date Date Reached TD Completion Date

API NO. 15- 193-20650000

County Thomas

115 S E/2 NE NE Sec. 5 Twp. 9S Rge. 31W

775' FNL Feet from S (circle one) Line of Section

330' FEL Feet from EW (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
NE, SE, NW or SW (circle one)

Lease Name CARR Well # 1-5

Field Name Wildcat

Producing Formation Lansing + Torontie

Elevation: Ground 3024 KB 3029

Total Depth 4750 PBTD \_\_\_\_\_

Amount of Surface Pipe Set and Cemented at 349 Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set Port Collar @ 2640' Feet

If Alternate II completion, cement circulated from 2640'  
feet depth to surface w/ 450 sx cmt.

Drilling Fluid Management Plan ALT 2 JK 12-16-96  
(Data must be collected from the Reserve Pit)

Chloride content 2000 ppm Fluid volume 1100 bbls

Dewatering method used KCC

Location of fluid disposal if hauled offsite: SEP 17

Operator Name RELEASED CONFIDENTIAL

Lease Name \_\_\_\_\_ License No. \_\_\_\_\_

Quar MAR 23 1998 Twp. \_\_\_\_\_ S Rng. \_\_\_\_\_ E/W

County \_\_\_\_\_ Docket No. \_\_\_\_\_

FROM CONFIDENTIAL

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature \_\_\_\_\_

Title Raul F. Brito, President Date 9/17/96

Subscribed and sworn to before me this 17th day of September 19 96.

Notary Public Betty M. Abbott MAILED

Date, Commission Expires January 22, 1999

NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 1-22-99

K.C.C. OFFICE USE ONLY			
F	<input checked="" type="checkbox"/>	Letter of Confidentiality Attached	
C	<input checked="" type="checkbox"/>	Wireline Log Received	
C	<input type="checkbox"/>	Geologist Report Received	
Distribution			
<input checked="" type="checkbox"/>	KCC	<input type="checkbox"/> SWC/...	<input type="checkbox"/> NGPA
<input type="checkbox"/>	KGS	<input type="checkbox"/> Plug	<input type="checkbox"/> Other (Specify)

SEP 18 1996  
09-18-1996  
CONSERVATION DIVISION  
Wichita, Kansas

Operator Name Brito Oil Company, Inc.

Lease Name Carr

Well # 1-5

Sec. 5 Twp. 9S Rge. 31W  
 East  
 West

County Thomas

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets.)  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No  
 Electric Log Run  Yes  No  
 (Submit Copy.)

Log Formation (Top), Depth and Datums  Sample  
 Name Top Datum

See attachment sheet

List All E.Logs Run: Dual Ind., Neutron/Density, Sonic

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8"	28#	349	60/40 Pozmix	185	2%gel, 4%cc
Production	7 7/8	5 1/2"	15.5#	4736'	ASC	200	6% calsea, 10% salt, 7#/sk gilsonite

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate				
Protect Casing	4262	common-A	50	(Squeeze)
Plug Back TD				
Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used) Depth	
3/ft.	4298-4304, 4176-4180		250 gal 15% INS 4340	
4/ft.	3986-3990			

TUBING RECORD		Size	Set At	Packer At	Liner Run				
127 jts		2 3/8	4136			<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Date of First, Resumed Production, SWD or Inj.				Producing Method					
7-5-96				<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)					
Estimated Production Per 24 hours	Oil	Bbls.	Gas	Mcf	Water	Bbls.	Gas-Oil Ratio	Gravity	
	130		=0-		trace			36	

Disposition of Gas:  
 Vented  Sold  Used on Lease  
 (If vented, submit ACO-18.)

METHOD OF COMPLETION  
 Open Hole  Perf.  Dually Comp.  Commingled  
 Other (Specify) \_\_\_\_\_

Production Interval  
3986' - 4304'

BRITO OIL COMPANY, INC.  
(Op. #4629)  
120 S. Market, Suite 300  
Wichita, Kansas 67202

#1-5 CARR

API # 15-193-20650000

**CONFIDENTIAL**

115' S E/2 NE NE

Sec. 5-9S-31W

Thomas County, Kansas

**ORIGINAL**

ACO-1 ATTACHMENT SHEET

SAMPLE TOPS			E-LOG TOPS	
Anhy	2629	(+ 400)	ANHY	
Top	3792	(- 763)	TOP	
HB	3996	(- 967)	HB	3994 (- 967)
LKC	4033	(- 1004)	LKC	4030 (-1001)
MC	4159	(- 1130)	MC	4158 (-1129)
STK	4248	(- 1219)	STK	4248 (-1219)
HUSH	4282	(- 1253)	HUSH	4281 (-1252)
BKC	4305	(- 1276)	BKC	4307 (-1278)
MARM	4431	(- 1302)	MARM	4330 (-1301)
PAW	4421	(- 1392)	PAW	4424 (-1395)
FS	4489	(- 1460)	FS	4490 (-1461)
CHER	4519	(- 1490)	CHER	4519 (-1490)
MISS	4635	(- 1606)	MISS	4626 (-1597)

DST #1 3850-3883 (Topeka)

30"-30", 30"-30" Rec. 130' VSOCW (1% oil),  
1380' SW. FP 93-352#, 447-634# SIP 1184-1184#

DST #2 4002-4040 (Tor. & LKC "A")

30"-45" 45"-60" Rec. 90' MO (80% oil, 20% M), 60' MO  
(65% oil), 60' SOCW (5% Oil), 60' VSOCW (1% oil)  
Cl 35,000, FP 52-62#, 93-124#, SIP 1277-1267#

DST #3 4046-4074 (LKC "B")

30"-45" 60"-60", Rec. 1080' GIP, 1380' CGO (35°),  
120' MGO (20% M, 15% G, 65% Oil), FP 93-239#,  
291-583#, SIP 1319-1319#

DST #4 4076-4090 (LKC "D")

30"-45" 60"-60" Rec. 2100' GIP, 720' CGO (35°),  
60' GMO (65% oil). FP 62-135#, 156-260#  
SIP 1070-1008#

DST #5 4094-4110 (LKC "E")

30"-45" 60"-60" Rec. 240' GIP, 100' FO (32°)  
50' WM (20% W), FP 52-52#, 62-62#, SIP 1254-1222#

DST #6 4165-4185 (LKC "H")

30"-45" 60"-60" Rec. 549' GIP, 976' FO (32°),  
61' OCM (40% Oil), FP 52-104#, 209-345# SIP 1275-1254#

DST #7 4188-4220 (LKC "I") 30"-30"-30"-30"/Rec: 15' OCM  
(30% oil). FP's 20-20#, 20-20#. SIP's 31-25#

DST #8 4280-4310 (LKC "L") 30"-45"-60"-60"/ Rec: 60' FO,  
90' OCM (40% oil). FP's 41-14#, 52-52#. SIP's 1150-1150#.

KCC

SEP 17

**CONFIDENTIAL**

**RELEASED**

**MAR 23 1998**

**FROM CONFIDENTIAL**

Rec'd  
**MAILED**

**SEP 18 1996**

CONSERVATION DIVISION  
Wichita, Kansas

# ALLIED CEMENTING CO., INC.

0279

ORIGINAL

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

15-193-20650-00-00

CONFIDENTIAL

SERVICE POINT:  
OKLEY, KS

DATE <u>5-30-96</u>	SEC. <u>5</u>	TWP. <u>9S</u>	RANGE <u>31W</u>	CALLED OUT	ON LOCATION <u>10:00 PM</u>	JOB START <u>11:30 AM</u>	JOB FINISH <u>12:00 AM</u>
LEASE <u>CARR</u>	WELL # <u>1-5</u>	LOCATION <u>OKLEY 12P-4E-14S</u>			COUNTY <u>THOMAS</u>	STATE <u>KS</u>	

OLD OR (NEW) (Circle one)

CONTRACTOR WHITE & ELLIS DRLLG.

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4" T.D. 350'

CASING SIZE 8 3/4" DEPTH 348

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 15'

PERFS.

OWNER SAME

CEMENT

AMOUNT ORDERED 185 SKS 60/40 PZ 48 CC 20 GEL

COMMON	<u>111</u>	<u>SKS</u>	@	<u>220</u>	<u>299 20</u>
POZMIX	<u>74</u>	<u>SKS</u>	@	<u>315</u>	<u>233 10</u>
GEL	<u>4</u>	<u>SKS</u>	@	<u>9 00</u>	<u>38 00</u>
CHLORIDE	<u>7</u>	<u>SKS</u>	@	<u>28 00</u>	<u>196 00</u>
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<u>185</u>	<u>SKS</u>	@	<u>1 05</u>	<u>194 25</u>
MILEAGE	<u>44</u>	<u>per 100 mile</u>			<u>125 80</u>

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

# 300 HELPER DEAN

BULK TRUCK

# 212 DRIVER JEFF

BULK TRUCK

# DRIVER

TOTAL 1,586 25

REMARKS:

Displacement 2 1/4 BBL.

SERVICE

CEMENT 120 CTRC.

DEPTH OF JOB	<u>348'</u>			
PUMP TRUCK CHARGE				<u>445 00</u>
EXTRA FOOTAGE	<u>48'</u>	@	<u>42</u>	<u>112</u>
MILEAGE	<u>17</u>	mile	@	<u>2 85</u>
PLUG	<u>8 3/4 SURFACE</u>	@		<u>45 00</u>
		@		
		@		

TOTAL 538 45

CHARGE TO: BRETO OIL COMP.

STREET 120 S. Market #300

CITY Wichita STATE Kansas ZIP 67202

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL

KCC  
SEP 17  
CONFIDENTIAL

RELEASED  
MAR 23 1998  
FROM CONFIDENTIAL

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 RECEIVED

SEP 18 1996

CONSERVATION DIVISION  
Wichita, Kansas

# ALLIED CEMENTING CO., INC. 0334

15-193-20650-00-00

ORIGINAL

PERMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT: Oakley

DATE <u>6-10-96</u>	SEC. <u>5</u>	TWP. <u>9</u>	RANGE <u>31</u>	CALLED OUT	ON LOCATION <u>11:50 AM</u>	JOB START	JOB FINISH <u>4:25 PM</u>
LEASE <u>Cagr</u>	WELL # <u>1-5</u>	LOCATION <u>Oakley 10N-4E-4S-WS</u>	COUNTY <u>Thomas</u>	STATE <u>Kan</u>			

OLD OR (NEW) (Circle one)

CONTRACTOR White + Ellis #9

TYPE OF JOB Production String

HOLE SIZE 7 7/8 T.D. 4730'

CASING SIZE 5 1/2 DEPTH 4736'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL Part Collar DEPTH 2640'

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 33.28'

CEMENT LEFT IN CSG. 33.28'

PERFS.

OWNER Same

CEMENT

AMOUNT ORDERED 210 SKS ASC  
7" prest Gilsomite, 25 BBL Salt Flush  
500 gal WFR-2

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
<u>ASC 210 SKS</u>	@	<u>8.20</u>	<u>1,827.00</u>
<u>500 gal WFR-2</u>	@	<u>1.00</u>	<u>500.00</u>
<u>Salt 15 SKS</u>	@	<u>7.00</u>	<u>105.00</u>
<u>Gilsomite 1470#</u>	@	<u>41¢</u>	<u>602.70</u>
	@		
HANDLING <u>210 SKS</u>	@	<u>1.02</u>	<u>220.80</u>
MILEAGE <u>4¢ per SK mile</u>			<u>142.80</u>
			TOTAL <u>3,398.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Walt

# 300 HELPER Terry

BULK TRUCK

# 305 DRIVER Jeff

BULK TRUCK

# DRIVER

REMARKS:

handed Plug 21300#

Float Held

10 SKS @ Water Well

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>1,156.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>19 miles</u>	@	<u>2.85</u> <u>48.45</u>
PLUG <u>5 1/2 Buldrec Plug</u>	@	<u>50.00</u>
	@	
	@	
		TOTAL <u>1,254.45</u>

CHARGE TO: Brito Oil Co.

STREET 120 S Meubot St 300

CITY Wichita STATE Kansas ZIP 67202

RELEASED

MAR 23 1998

FROM CONFIDENTIAL

FLOAT EQUIPMENT

<u>5 1/2</u>		
<u>1- Guide Shoe</u>	@	<u>168.00</u>
<u>1- AFU Insert</u>	@	<u>263.00</u>
<u>2- Baskets</u>	@	<u>284.00</u>
<u>10- Centralizers</u>	@	<u>560.00</u>
<u>1- Part Collar</u>	@	<u>2,340.00</u>
		TOTAL <u>3,615.00</u>

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

Rec'd  
~~MAILED~~

SEP 18 1996

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE

T. E. Janson

# ALLIED CEMENTING CO., INC.

15-193-20650-00-00

0473

ORIGINAL

PERMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT:

Oakley

DATE <u>6/20/96</u>	SEC. <u>5</u>	TWP. <u>7s</u>	RANGE <u>31w</u>	CALLED OUT	ON LOCATION <u>3:00 PM</u>	JOB START <u>4:20 PM</u>	JOB FINISH <u>5:30 PM</u>
LEASE <u>Carr</u>	WELL # <u>1-5</u>	LOCATION			COUNTY <u>Thomas</u>	STATE <u>KS</u>	

OLD OR NEW (Circle one)

CONTRACTOR \_\_\_\_\_ OWNER SAM T

TYPE OF JOB Cmt Port Collar CEMENT \_\_\_\_\_

HOLE SIZE 5 1/2 T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH 4736

TUBING SIZE 2 3/4 4.6" DEPTH \_\_\_\_\_

DRILL PIPE DEPTH \_\_\_\_\_

TOOL Port Collar DEPTH 2640

PRES. MAX 1920 MINIMUM 100

MEAS. LINE SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

AMOUNT ORDERED  
450 sks 60/40 + 870 gal 1/4" Flo-Seal  
used 350 sks 60/40 + 870 gal 1/4" Flo-Seal

COMMON 210 SKS @ 7.20 1,512.00

POZMIX 140 SKS @ 3.15 441.00

GEL 24 SKS @ 9.50 228.00

CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_

Flo-Seal 88# @ 1.15 101.20

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

HANDLING 450 SKS @ 1.05 472.50

MILEAGE 4¢ per sk/mile 306.00

TOTAL 3,060.20  
KCC

EQUIPMENT

PUMP TRUCK CEMENTER Max

# 102 HELPER Walt

BULK TRUCK \_\_\_\_\_

# 303 DRIVER Pearl

BULK TRUCK \_\_\_\_\_

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

SERVICE

SEP 17

Open Tool Establish rate up ANN. Mix Cmt  
350 sks 60/40 + 870 gal 1/4" Flo-Seal Cmt  
Discalated to surface. Switch to Displacement  
Displace to BAL Close Tool Test to 1500 PSI  
Tool Held Run in 2 1/2 hrs & Reverse Hole  
Clear

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE 550.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 17 - mi @ 2.85 48.45

PLUG \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 598.45

CONFIDENTIAL

CHARGE TO: Brito Oil Co

STREET 120 S. Market # 300

CITY Wichita STATE Kan ZIP 67202

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

RELEASED

MAH 23 1998

FROM CONFIDENTIAL

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Earl Ewas

~~MAILED~~  
Rec'd  
SEP 18 1996

CONSERVATION DIVISION  
Wichita, Kansas

# ALLIED CEMENTING CO., INC.

0474

15-193-20650-00-00

P.O. BOX 31  
RUSSELL, KANSAS 67665

**CONFIDENTIAL**

SERVICE POINT:

**ORIGINAL**

*Oakley*

DATE <i>12/25/90</i>	SEC. <i>5</i>	TWP. <i>7S</i>	RANGE <i>31W</i>	CALLED OUT	ON LOCATION <i>10:30AM</i>	JOB START <i>11:00AM</i>	JOB FINISH
TYPE <i>Case</i>	WELL # <i>1-5</i>	LOCATION <i>Oakley</i>	COUNTY <i>Thomas</i>	STATE <i>Ks</i>			

OLD OR NEW (Circle one)

CONTRACTOR	OWNER <i>Samm C</i>
TYPE OF JOB <i>Saucozt</i>	CEMENT
HOLE SIZE	T.D.
CASING SIZE <i>5 1/2</i>	DEPTH <i>4736</i>
TUBING SIZE <i>2 3/8</i>	DEPTH <i>4262</i>
DRILL PIPE	DEPTH
TOOL <i>Cat Retainer</i>	DEPTH <i>4262</i>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	

AMOUNT ORDERED		
<i>50 SKS CLASS A</i>		
COMMON	<i>50 SKS @ 7.20</i>	<i>360.00</i>
POZMIX	<i>1 @</i>	
GEL	<i>1 @</i>	
CHLORIDE	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
HANDLING	<i>50 SKS @ 1.05</i>	<i>52.50</i>
MILEAGE	<i>4¢ per SK/mile</i>	<i>80.00</i>
TOTAL		<i>492.50</i>

**EQUIPMENT**

PUMP TRUCK	CEMENTER <i>Max</i>
# <i>102</i>	HELPER <i>Walt</i>
BULK TRUCK	
#	DRIVER
BULK TRUCK	
#	DRIVER

**REMARKS:**

*Pump down thg 2 MBL/min 1000 psi would not communicate Pump down ANN 2 MBV min 700 PSI would not communicate set cement retainer Circulate hole clean, set in retainer, took rate: 3 BPM 2 600 psi, mixed 50 SKS cement had circ all times. Pulled up to 3814' Circ hole clean, pulled 3 1/2 hrs. Pressured to 800 psi, shut in. shut in*

**SERVICE**

DEPTH OF JOB	<i>4262</i>	<i>550.00</i>
PUMP TRUCK CHARGE		
EXTRA FOOTAGE	<i>1 @</i>	
MILEAGE	<i>17 - Mi @ 2.25</i>	<i>48.75</i>
PLUG	<i>1 @</i>	
	<i>1 @</i>	
TOTAL		<i>598.75</i>

CHARGE TO: *Brita Oil Co.*  
STREET *120 S Mendot # 300*  
CITY *Wichita* STATE *Kansas* ZIP *67202*

**FLOAT EQUIPMENT**

	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
	<i>1 @</i>	
TOTAL		

**RELEASED**

**MAR 23 1998**

**FROM CONFIDENTIAL**

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE

*Earl Exner*

TAX \_\_\_\_\_  
TOTAL CHARGE \_\_\_\_\_  
DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

*Rec'd*  
~~MAILED~~

SEP 18 1996

CONSERVATION DIVISION

KCC

112

**CONFIDENTIAL**