

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,615 -00-00

LEASE NAME Dechert

WELL NUMBER 1

1980 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 32 TWP. 9S RGE. 31 (E/W)

COUNTY Thomas

Date Well Completed 10/7/93

Plugging Commenced 10/7/93

Plugging Completed 10/7/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Castle Resources, Inc.

ADDRESS 1200 E. 27th, Suite C, Hays, KS 67601

PHONE#(913) -625-5155 OPERATORS LICENSE NO. 9860

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-7-93 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	265'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4670'-2625' 10 sks cement @ 40'

10 sks cement @ 2625' 15 sks in rathole

40 sks cement @ 1500'

100 sks cement @ 315'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) [Signature] STATE CORPORATION COMMISSION

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

RECEIVED
OCT 11 1993
STATE CORPORATION COMMISSION



AND SWORN TO before me this 7th day of October

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: 2-6-96

15-193-20615-00-00

EMPHASIS OIL OPERATIONS
A Division of N-B Company, Inc.
P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Castle Resources, Inc.
1200 E. 27th, Suite C
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Dechert

WELL #1

LOCATION: C E/2 E/2 NW
Section 32-9S-31W
Thomas County, Kansas

LOGGERS TOTAL DEPTH: 4673'

ROTARY TOTAL DEPTH: 4670'

COMMENCED: 9/30/93

CASING: 8-5/8" @ 265' w/180 sks cement

ELEVATION: 3041' K.B.

COMPLETED: 10/7/93

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	1705'	Shale & Lime	3020'
Shale	1765'	Lime & Shale	3245'
Cedar Hills	2329'	Shale & Lime	4063'
Shale	2420'	Lime & Shale	4328'
Anhydrite	2614'	R.T.D.	4670'
Shale	2645'		


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on October 7, 1993.

My commission expires: February 6, 1996.




Glenda R. Tiffin, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1993
10-11-1993
CONSERVATION DIVISION
Wichita, Kansas