


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Thomas County, Sec. 1 Twp. 9S Rge. 33 (W) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Wycoff-Williams Drilling Company
Lease Name B. Chase Well No. 1
Office Address Box 170, Grinnell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 26, 1952
Application for plugging filed September 26, 1952
Application for plugging approved September 26, 1952
Plugging commenced September 27, 1952
Plugging completed September 27, 1952
Reason for abandonment of well or producing formation No commercial showings of oil or gas were found.
If a producing well is abandoned, date of last production Non-producer 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation None Depth to top - Bottom - Total Depth of Well 4834 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	70'	145'	8 5/8"	221	None
Sand	Water	1670'	1890'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 220 feet to 30 feet for each plug set.
Wooden plug at bottom of surface pipe with 15 sacks of cement on top, then - 30 feet from top of surface another wooden plug was set and 10 more sacks of cement brought cement to top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wycoff-Williams Drilling Company
Address Box 170, Grinnell, Kansas

STATE OF Kansas, COUNTY OF Gove, ss.
Wesley E. Williams, partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wesley E. Williams
Box 170, Grinnell, Kansas (Address)

Harley L. McQuinn Notary Public.



PLUGGING
FILE SEC L Y 9 R 3324
BOOK PAGE 18 LINE 42

RECEIVED
OCT - 1 1952
10-01-1952
CONSERVATION DIVISION
Wichita, Kansas

15-193-00011-00-00

DRILLERS WELL LOG

September 30, 1952

Company Wycoff-Williams Drilling Co.

Sec. 1 Twp. 9S Rge. 33W

Farm B. Chase

Well No. 1 NE NE SE

Total Depth Rotary 4834

County Thomas

Comm. 9/9/52 Comp. 9/27/52

State Kansas

Shot or Treated None

Contractor Company Tools

Casing: 8 5/8" 221' Cemented

Elevation 3107

Production Dry

Figures Indicated Bottom of Formations

Surface soil & clay	0-70	Lime & Shale	3700
Sand	145	Shale & Lime	3810
Sand & Gravel	171	Lime & Shale	3975
Shale	221	Lime	4070
Shale & Shells	945	Lime, brkn.	4150
Shale & lime Streaks	1455	Lime & Shale	4175
Shale & Shells	1670	Lime	4240
Sand	1890	Lime & Shale	4265
Shale	2165	Lime	4290
Lime Streaks	2210	Shale & Lime	4340
Shale	2305	Lime & Shale	4375
Anhydrite	2335	Lime & Shale	4455
Red bed & Shale	2655	Lime & Shale	4500
Lime	2745	Lime & Shale	4530
Lime & Shale	2890	Lime & Shale	4580
Shale & red bed	2925	Lime & Shale	4620
Shale	3110	Lime	4650
Lime	3200	Lime	4690
Lime, Shale, & red bed	3280	Lime & Shale	4725
Lime & Shale	3350	Lime	4740
Lime & Shale	3425	Lime	4755
Shale & Lime	3505	Lime & Shert	4776
Shale	3545	Lime & Shert	4790
Lime	3585	Lime	4825
		Lime	4834

RECEIVED
 STATE CORPORATE COMMISSION
 OCT - 1 1952
 CONSERVATION DIVISION
 Wichita, Kansas
 10-01-1952

PLUGGING
 LINE 372 179 R 332
 ROCK FROM LINE 17

Total Depth 4834

Page #2
Drillers Well Log
NE NE SE 1-9-33
Thomas County, Kansas
B. Chase #1

TOPS

Topeka lime	3854	No show of oil
Heebner shale	4036	
Lansing-Kansas City lime	4076	No show of oil
Marmaton lime	4378	Slight stain at 4620
Mississippi lime	4671	No show of oil

STATE OF Kansas, COUNTY OF Gove, ss.

Wesley E. Williams, (partner) Wycoff-Williams Drilling Co. owner of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Wesley E. Williams

Box 170, Grinnell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 52

Harley L. McQuinn
Notary Public

My commission expires June 13, 1956

