


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Thomas County. Sec. 25 Twp. 9 Rge. 33 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner Hellar Drilling Company, Inc.
Lease Name Herbel Well No. 1
Office Address 1014 Union Center Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-25 19 68
Application for plugging filed 6-25 19 68
Application for plugging approved 6-25 19 68
Plugging commenced 6-25 19 68
Plugging completed 6-25 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8	312	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set at 1785 with 70 sacks cement, 6% gel
2nd. plug was set at 330' with 20 sacks cement, 6% gel
3rd. plug was set at 40' with 10 sacks cement, 6% gel
Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1968
CONSERVATION DIVISION
Wichita, Kansas
06-27-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L.J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and Sworn to before me this 25th day of June, 19 68
Joseph A. Hess
JOSEPH A. HESS Notary Public.

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15-193-20003-00-00

WELL LOG

Company	Hellar Drilling Company, Inc. 1014 Union Center Bldg. Wichita, Kansas 67202	Sec. 25	Twp. 9	Rng. 33
Farm	Herbel No. 1	Location	NE NE NE	
Total Depth	4725'	County	Thomas	
Comm.	6-11-68 Comp. 6-25-68	Elevation:	3113' K.B.	3110' D.F.
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		3108' G.R.	
	Casing Record 312' - 8 5/8"	Cement Record 265 sacks cement	Production:	D & A

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Clay
40'	250'	Sand & Clay
250'	260'	Shale
260'	312'	Shale
312'	1300'	Shale
1300'	2001'	Shale & Sand
2001'	2280'	Shale & Shells
2280'	2410'	Shale & Gyp
2410'	2640'	Shale & Gyp
2640'	2651'	Shale
2651'	2696'	Anhy.
2696'	3172'	Lime & Shale
3172'	3200'	Lime
3200'	3450'	Lime & Shale
3450'	3550'	Lime & Shale
3550'	3695'	Lime
3695'	4725'	Lime
4725'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1968
CONSERVATION DIVISION
Wichita, Kansas

06-27-1968

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Herbel #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 25th of June 1968.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970

