

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,577
LEASE NAME Lunsway
WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2,310 Ft. from S Section Line
2,310 Ft. from E Section Line
SEC. 32 TWP. 9S RGE. 33 (R) or (W)
COUNTY Thomas
Date Well Completed 11-4-91
Plugging Commenced 11-4-91
Plugging Completed 11-4-91

LEASE OPERATOR John O. Farmer, Inc.
ADDRESS Box 352, Russell, KS. 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-4-91 (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,771'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	368'	Cmtd. w/230 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,700' thru drill pipe. Spot 100 sax cement @1,885' thru drill pipe. Spot 40 sax cement @420' thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Cement is 60-40 Pozmix w/6% gel and 1/4# flo-seal per sack. (If additional description is necessary, use BACK of this form.)
Plug down at 9 PM.

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas.

(Address) Shields Bldg., Russell, KS.

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 91

Ruth Phillips
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1991
11-20-1991
CONSERVATION DIVISION
Wichita, Kansas


My Commission Expires:

RUTH PHILLIPS
State of Kansas
My Appt. Exp. 5-26-95

WELL LOG

Operator: John O. Farmer, Inc.
Well: Lunsway #1
Commenced: October 25, 1991
Completed: November 4, 1991
Contractor: Shields Drilling Co.

Well Description: NW NW SE
Sec. 32-9S-33W
Thomas Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	368'	Cmtd. w/230 sax

Elevation: 3,186' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & Shale	2,140'
Shale	2,698'
Anhydrite	2,729'
Shale	3,447'
Shale & Lime	4,063'
Lime	4,771' RTD

Notes

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1991

11-20-1991
CORPORATION DIVISION
Wichita, Kansas