

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-193-20,660-00-00

LEASE NAME Kistler

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1-14

1140' Ft. from N Section Line

1170' Ft. from E Section Line

SEC. 14 TWP. 9S RGE. 34 (E) or (W)

COUNTY Thomas

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main Suite 801

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D/A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 03-13-97

Plugging Commenced 03-13-97

Plugging Completed 03-13-97

The plugging proposal was approved on 03-10-97 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached?

Producing Formation  Depth to Top  Bottom  T.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	351'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Fill with heavy mud, 1st plug from 2745'-2645' with 25 sks, 2nd plug from 1770'-1370' with 100 sks, 3rd plug from 400'-240' with 40 sks, 4th plug from 40'-0' with 10 sks, 15 sks in rathole, total 190 sks 60/40 pos, 6% gel, 1/4# floseal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Mark Galyon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 150 N. Main, Ste 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of March, 19 97

[Signature]  
Notary Public

My Commission Expires: 3-1-2000

