

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
APR 17 1969
CONSERVATION DIVISION
Wichita, Kansas

04-17-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20200-00-00

Operator's Full Name Koch Exploration Company,

Complete Address: P. O. Box #2256, Wichita, Kansas.

Lease Name Wiggington Well No. 1

Location CNE-SE Sec. 13 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 3:00PM Day 14 Month 4 Year 1969

The Above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru
DP from 1550' to 1225'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 4/17/69
INV. NO. 9613-W