

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1965
08-30-1965
CONSERVATION DIVISION
Wichita, Kansas

15 ~~18~~-179-30008-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Schwarz Well No. 1

Location CSE-SE Sec. 34 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4825

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 12:30AM Day 27 Month 8 Year 1965

The Above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 140 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 220', set plug with 1/2 sack hulls and

displaced 20 Sx. cement thru DP. Heavy mud to 40', set plug with

1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 8/30/65
INV. NO. 1711-W