

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20033-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas
09-21-1970

Operator's Full Name Mull Drilling Company, Incorporated,
Complete Address 1625 Wichita Plaza Building, Wichita, Kansas.
Lease Name Schwartz Well No. 2
Location CNE-SW Sec. 1 Twp. 9 Rge. (E) (W) 31
County Thomas Total Depth 4098'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Rains and Williamson Oil Company, Incorporated.
Address 1625 Wichita Plaza Building, Wichita, Kans. License No.
Operation Completed: Hour 5:30 PM Day 18 Month 9 Year 1970

The above well was plugged as follows:

288'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1325'.
Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru
DP from 1550' to 1225'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9-21-70
INV. NO. 2561-W