

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1972
CONSERVATION DIVISION
Wichita, Kansas

15-193-20039-00-00

02-16-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Lewis Mull,

Complete Address 415 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name Johnson Well No. 1

Location CE/2-NE-SW Sec. 3 Twp. 9 Rge. (E) (W) 31

County Thomas Total Depth 4315'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1425 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 4:30 PM Day 13 Month 2 Year 1972

The above well was plugged as follows:

286'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 2-17-72
INV. NO. 5185-W