

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20005-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1968
CONSERVATION DIVISION
Wichita, Kansas
09-30-1968

Operator's Full Name Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza B building, Wichita, Kansas.

Lease Name Spadaro Well No. 1

Location CSE-NW Sec. 4 Twp. 9 Rge. (E) (W) 31

County Thomas Total Depth 4360'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company, Incorporated,

Address: 1425 Wichita Plaza Building, Wichita, Kansas License No.

Operation Completed: Hour 1:45AM Day 27 Month 9 Year 1968

The Above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1580' and displaced 100 Sx. cement thru
DP from 1580' to 1255'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridgen @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 9/30/68
INV. NO. 8542-U