

KANSAS

M

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

DEC 3 1968
CONSERVATION DIVISION
Wichita, Kansas

15-193-20008-00-00

12-03-1968

Operator's Full Name Norman D. Fitzgerald,

Complete Address: P. O. Box #5046, Abilene, Texas.

Lease Name James Well No. 1

Location SE-SE Sec. 4 Twp. 9 Rge. (E) (W) 31

County Thomas Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Kans License No. _____

Operation Completed: Hour 7:00 PM Day 28 Month 11 Year 1968

The Above well was plugged as follows:

232'--8 5/8" Surface pipe, cement circulated with 190 Sx.
Top of Dakota section @ 1295'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru
DP from 1525' to 1200'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. B. Nichols*
Well Plugging Supervisor

DATE 12/3/68
INV. NO. 8939-W