

KANSAS

P STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
OCT 30 1972

CONSERVATION DIVISION
Wichita, Kansas
10-30-1972

193 20044
15-~~119~~-~~200044~~-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Evans Well No. 1

Location NW-NE Sec. 5 Twp. 9 Rge. (E) (W) 31

County Thomas Total Depth 4325'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30 PM Day 28 Month 10 Year 1972

The above well was plugged as follows:

260'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 110 Cu. Ft. cement
thru DP from 1675' to 1350'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/30/72
INV. NO. 6546-w