

KANSAS

Form CP-3  
Rev. 6-26-62

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20003-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
06-27-1968

Hellar Drilling Co. Inc.

Operator's Full Name Winwell 1968 Exploration Company,

Complete Address: 1011 Commercial National Bank Building, Shreveport, Louisiana.

Lease Name Herbel Well No. 1

Location NE-NE-NE Sec. 25 Twp. 9 Rge. (E) (W) 33

County Thomas Total Depth 4725

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.     

Operation Completed: Hour 5:00 AM Day 25 Month 6 Year 1968

The Above well was plugged as follows:

312'--8 5/8" Surface pipe, cement circulated with 265 Sx.  
Top of Dakota section @ 1560'.

Circulated hole with heavy mud. Pulled DP to 1785 and displaced 100 Sx. cement thru  
DP from 1785' to 1460'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from  
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor.

INVOICED

DATE 6-27-68

INV. NO. 8013-W