

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1970
CONSERVATION DIVISION
Wichita, Kansas
03-09-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20027-00-00

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Ross Well No. A-1

Location CNE-SW Sec. 25 Twp. 9 Rge. (E) (W) 33

County Thomas Total Depth 4877'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:00 PM Day 6 Month 3 Year 1970

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 220 Sx.
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 100 Sx. cement thru
DP from 1800' to 1475'. Pulled DP to 330' and displaced 25 Sx. cement thru DP from
330' to 255'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 3-9-70
INV. NO. 1562-w