

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20038-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
11-29-1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name U. S. Signal Oil & Gas Company 1971 Program,

Complete Address 125 Central Building, Midland, Texas.

Lease Name Signal 71 Penney Well No. 1

Location NE-NE Sec. 31 Twp. 9 Rge. (E) (W) 36

County Thomas Total Depth 5680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 4:45 PM Day 25 Month 11 Year 1971

The above well was plugged as follows:

454'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota Section @ 1670' (Electric Log).

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 115 Sx. cement thru
DP from 1925' to 1650'. Pulled DP to 475' and displaced 25 Sx. cement thru DP from
475' to 400'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. P. Scholz
Well Plugging Supervisor

DATE 12-1-71

INV. NO. 4742-W