

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20447-0000

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1972
07-07-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801
501 Union Center Wichita, Kansas

Lease Name Zeigler Well No. 2

Location SW SE SE Sec. 4 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3445'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co Tools

Address License No.

Operation Completed: Hour 9 A Day 5 Month 7 Year 1972

The above well was plugged as follows:

RTD 3445' 8 5/8 csg set at 248' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed:
Well Plugging Supervisor

INVOICED

DATE 7/7/72

INV. NO. 6004-W