


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rocks _____ County. Sec. 18 Twp. 10S Rge. 16 (X) W (W)
Location as "NE/CNW%SW%" or footage from lines C NW NE
Lease Owner Davis Bros.-Transit Corporation
Lease Name Fritts "A" Well No. 1
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 7, 19 59
Application for plugging filed October 7, 19 59
Application for plugging approved October 7, 19 59
Plugging commenced October 7, 19 59
Plugging completed October 7, 19 59
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty-Box 326-Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	106'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 350'; set plug, cemented with 20 sacks cement.
Filled hole with heavy drilling mud to 105'; set plug, cemented with 15 sacks cement.
Filled hole with heavy drilling mud to 40'; set plug, cemented with 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Paul E. Gathers

(Address) _____

SUBSCRIBED AND SWORN to before me this 26th day of October, 19 59

My commission expires May 17, 1962

Mildred Jean
Notary Public.



15-163-00934-00-00

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation - Fritts "A" # 1 well located in
C NW NE Section 18-10S-16W
Rooks County, Kansas

Commenced: September 29, 1959
Completed: October 7, 1959
Elevation: 1948' KB

Casing 8 5/8" @ 106'
Cemented w/85 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Summary of Formation</u>	
Sand	0	77	Anhydrite	1152'
Shale	77	107	Topeka	2860'
Shale and shells	107	700	Heebner	3090'
Sand	700	850	Toronto	3110'
Shale	850	870	Lansing	3131'
Red bed shale	870	1156	Base of K.C.	3375'
Anhydrite	1156	1194	Arbuckle	3476'
Shale	1194	1230		
Shale and shells	1230	1780		
Lime	1780	1965		
Shale w/lime	1965	2165		
Lime and shale	2165	2180		
Shale	2180	2340		
Lime and shale	2340	2475		
Shale	2475	2725		
Shale w/lime streaks	2725	2980		
Lime	2980	3064		
Lime and shale	3064	3134		
Lime	3134	3348		
Lime and shale streaks	3348	3400		
Lime	3400	3447		
Conglomerate and chert	3447	3476		
Lime	3476	3506 TD		

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 26th day of October, 1959.

My Commission expires May 17, 1962.

TRANSIT CORPORATION

BY Paul E. Gasters

Walter Dean
Notary Public

RECEIVED
STATE COMMISSION

JAN 21 1960
01-21-1960
CONSERVATION DIVISION
Wichita, Kansas

