

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20401-00-00
Spot: NWNE Sec/Twnshp/Rge: 36-19S-1W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DIENER Well #: 1
County: MCPHERSON Total Vertical Depth: 2980 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2978		125 SX
SURF	8.625	219		125 SX

96.85

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/16/2008 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (620) 628-4424

Proposed Plugging Method: PLACE 50' SAND PLUG OVER PERFS. FILL HOLE WITH MUD AND SET A 35 SX PLUG @ 470' AND FILL TO SURFACE WITH CEMENT.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 06/16/2008 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS, AND DUMP BAILED 4 SACKS CEMENT ON TOP. CUT CASING @ 500', LAID DOWN 17 JOINTS OF 4-1/2" CASING. RIH W/2" TUBING @ 470', UNITED CEMENTING & ACID COMPANY MIXED & PUMPED 175 SACKS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED TO SURFACE.

Perfs:

INVOICED
DATE 7-15-08
INV. NO. 2009060106

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 03 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED CEMENTING TICKET #8495. PLUG GOWN 1100, 6-16-2008

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PKS