

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20870-00-00
Spot: S2N2NE Sec/Twnshp/Rge: 31-18S-2W
4301 feet from S Section Line, 1279 feet from E Section Line
Lease Name: ANDERSON B Well #: 4
County: MCPHERSON Total Vertical Depth: 2390 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2380		75 SX
SURF	8.625	130		100 SX

77.68

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2008 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (620) 654-7149

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2008 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2208' AND CAP WITH 4 SX'S CEMENT, ATTEMPT TO PULL CASING -PARTED @ 150'. RUN 2" TUBING GDOWN 4.5" TO 450'. RUN 1" TUBING DOWN BACKSIDE OF 4.5" TO 450'. PUMP CEMENT DOWN 2" TUBING, STARTED TO GET PARTIAL RETURNS FROM 1". PUMPED APPRO. 25 BB'LS DOWN 1". PULLED BOTH STRINGS OF TUBING AND TOPPED OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
2314	2320		LANSING/KC

INVOICED
DATE 7-15-08
INV. NO. 2009060106

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 03 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 PO 4% GEL. COPELAND CEMENT TICKET #32348. USED 162 SX'S TOTAL

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)