

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22883-00-00

Spot: NENWNE

Sec/Twnshp/Rge: 34-16S-12W

4950 feet from S Section Line, 1320 feet from E Section Line

Lease Name: FELTES

Well #: 1-A

County: BARTON

Total Vertical Depth: 3363 feet

Operator License No.: 4871

Op Name: HITSCHMANN, CURTIS LEE DBA CURT

Address: 742 N US HWY 281
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3359	0	100 SX
SURF	8.625	250	0	160 SX

109.30

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/26/2008 8:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: CURTIS HITSCHMANN

Company: CURT'S OIL OPERATIONS

Phone: (620) 793-2540

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 7 sxs gel - 500# hulls.
Perfs at 1500' - 800' - 250'.

Plugging Proposal Received By: BRUCE RODIE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/26/2008 1:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3000' - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 2730' - pumped 7 sxs gel.
Pulled to 1550' - pumped 130 sxs cement with 200# hulls - circulated cement to surface.
Pulled tubing - tied to casing - pumped 40 sxs cement - circulated out backside.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3359	3360		
3302	3306		

INVOICED

DATE 7-15-08

INV. NO. 2009060107

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING-TICKET #35200.

JUL 03 2008

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

JUL 01 2008

ASSOCIATES OIL & GAS, INC.
555 N. WOODLAWN, #114

#1 "A" FELTES

34-16-12W
75' SE,
C NE NW NE


WICHITA, KS 67208

CONTR HUSKY DRILLING CO., INC. CTY BARTON

GEOL _____ FIELD BEAVER SOUTH

E 1898 KB CM 9/4/82 CARD ISSUED 10/14/82 IP P 60 80 & 4 BWPD
ARB OH 3359-3363

API 15-009-22,883



LOG Tops Depth/Datum

TOP	2684- 786
HEEB	2965-1067
TOR	2980-1082
BR LM	3056-1158
LANS	3074-1176
CONG	3321-1423
REW ARB	3332-1434
ARB	3337-1439
RTD	3363-1465

8 5/8 " 250; 4 1/2 " 3359

NO DSTS

MICT - CO. (ARB OH) SWB DWN, AC 500G, R&T, POP, P 60
BOPD & 4 BWPD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
OCT 15 1982
WICHITA, KANSAS

RECEIVED
OCT 15 1982
WICHITA, KANSAS

RECEIVED
OCT 15 1982
WICHITA, KANSAS