

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21151-00-01

Spot: NESWNE

Sec/Twnshp/Rge: 35-17S-12W

3687 feet from S Section Line, 1709 feet from E Section Line

Lease Name: SCHNEWEIS

Well #: 2

County: BARTON

Total Vertical Depth: 3394 feet

Operator License No.: 31714

Op Name: NOVY OIL & GAS, INC.

Address: 125 N MARKET STE 1230

WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3392	0	150 SX
SURF	8.625	283	0	165

110.31

Well Type: SWD

UIC Docket No: D19446.0

Date/Time to Plug: 06/26/2008 1:00 PM

Plug Co. License No.: 31714

Plug Co. Name: NOVY OIL & GAS, INC.

Proposal Rcvd. from: MICHAEL NOVY

Company: NOVY OIL & GAS, INC.

Phone: (316) 365-4651

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 14 sxs gel - 500# hulls.
Perfs at 1510' - 785' - 330'.

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/26/2008 5:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3380' - pumped 50 sxs cement with 100# hulls.
Pulled to 2970' - pumped 14 sxs gel.
Pulled to 1520' - pumped 210 sxs cement with 300# hulls.
Pulled to 340' - pumped 60 sxs cement - circulated to surface.
Pulled tubing - topped off with 5 sxs cement.
Backside full - pressured up.

Perfs:

Top	Bot	Thru	Comments
373	406		250 SX

INVOICED

DATE 7-15-08

INV. NO. 2007060109

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING-TICKET #35201.

JUL 03 2008

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

JUL 01 2008

C OIL, INC.

5-1 PETROLEUM BLDG.

#2 SCHNEWEIS

35-17-12W

NE SW NE

WICHITA, KS.

CONTR B & B DRILG., INC.


CTY BARTON

GEOL CAPL TODD

FIELD SNOW WHITE CONF

E 1870 KB CM 3/23/77 CARD ISSUED 5/26/77 IP P 30 BOPD. NW

ARB OH 3392-94



API 15-009-21,151

LOG	TOPS	DEPTH	DATUM
TOP		2689	- 819
HEEB		2981	-1111
BR LM		3095	-1225
LKC		3100	-1230
BKC		3327	-1457
ARB		3389	-1519
RTD		3394	-1524

8-5/8" 283/165sx, 5 1/2" 3392/150sx
 DST (1) 3089-3180/45-45-45-45, 30'M
 (NS) SIP 234-152# FP 112-112# 11'
 122# BHT 98°
 DST (2) 3266-3320/45-45-10-15, 30'M,
 SIP 91-91# FP 81-91# 91-91# BHT
 100°
 DST (3) 3352-94/60-45-60-45, 80'HOOM,
 300'MO, SIP 906-886# FP 61-102#
 152-173# BHT 110°
 MICT - CO TD, SWB 1.16 BOPH, N/W, AC
 250, REC LD, SWB 2 1/2 BOPH, N/W, AC 500
 REC LD, SWB 2-1/3 BOPH/5 HRS, SD/ON FU
 1100' OIL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS