

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23736-00-00

Spot: S2SEWNNE

Sec/Twnshp/Rge: 14-10S-19W

4000 feet from S Section Line, 1650 feet from E Section Line

Lease Name: PELTON A

Well #: 2

County: ROOKS

Total Vertical Depth: 3490 feet

Operator License No.: 33864

Op Name: HABIT PETROLEUM, LLC

Address: 639 280TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305		

113.43

Well Type: DH

UIC Docket No:

Date/Time to Plug: 06/21/2008 5:00 PM

Plug Co. License No.: 33493

Plug Co. Name: AMERICAN EAGLE DRILLING LLC

Proposal Rcvd. from: MIKE GASCHLER

Company: HABIT PETROLEUM, LLC

Phone: (785) 625-6190

Proposed
Plugging
Method:

Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack - 3% cc on side.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/22/2008 11:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Lost circulation - left 14 drill collars and one joint drill pipe in the hole.

T.O.F. 2994'.

1st. Plug at 2688' w/40 sxs - 3% cc.

2nd. Plug at 1465' w/25 sxs - 3% cc.

3rd. Plug at 813' w/100 sxs - 3% cc.

4th. Plug at 355' w/40 sxs - 3% cc.

5th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

INVOICED

DATE

7-21-08

INV. NO.

2009060128

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 09 2008

CONSERVATION DIVISION
WICHITA, KS

PJT

JUL 07 2008