

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30336-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 4-6S-20W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: STEELE Well #: 2  
County: ROOKS Total Vertical Depth: 1500 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1520	0	w/35 sxs cmt
SURF	8.625	175	0	w/175 sxs cmt

Well Type: SWD UIC Docket No: D15206.0 Date/Time to Plug: 06/09/2008 1:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Old information: SWD Cedar Hills Perfs 1363' - 1388'.  
Fluid 300' from surface.  
Pulled 52 joints 2" new upset tubing. 11.50 V thread - approximately 1300'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2008 3:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied took injection rate - 3 BPM 100#.  
Allied pumped 80 sxs 60/40 pozmix - 4% gel with 500# hulls.  
Max. P.S.I. 700#. S.I.P. 700#.  
Backside full of cement. Cement in head.

Perfs:

Top	Bot	Thru	Comments
1363	1388	DP	

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3 PAT

JUN 23 2008