

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21302-00-00
Spot: SWSWE Sec/Twnshp/Rge: 4-6S-20W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STEELE A Well #: 1
County: ROOKS Total Vertical Depth: 3643 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3641	0	w/125 sxs cmt
SURF	8.625	252	0	w/170 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2008 3:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-7218

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 4% gel - 11 sxs gel spacer - 500# hulls.
Fluid 100' from surface.
No squeeze records. Need to perforate Anhy and Base Dakota.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2008 7:20 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated two holes at 1775' and 1100'.
Ran tubing to 3628' - pumped 9 sxs gel spacer - followed with 40 sxs 60/40 pozmix - 4% gel with 150# hulls.
Pulled tubing to 1800' - pumped 105 sxs cement with 350# hulls - circulated cement.
PTOH. 4 1/2" casing broke off level with 8 5/8" braden head.
Topped off 4 1/2" casing with 10 sxs - casing full.
Hooked up to backside - pumped 100 sxs down backside.
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3641	3643	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

JUN 23 2008

PR