

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20596-00-00
Spot: NESENE Sec/Twnshp/Rge: 2-23S-2W
3616 feet from S Section Line, 347 feet from E Section Line
Lease Name: DETTWEILER Well #: 1
County: HARVEY Total Vertical Depth: 3272 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------|
| PROD | 5.5 | 3206 | | 125 SXS CMT |
| SURF | 8.625 | 206 | | 150 SXS CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PBTD @ 2,997', SAND TO 2,900' & TOP WITH 5 SXS. CEMENT. PERFORATE CASING @ 400'. CIRCULATE CEMENT FROM 400' TO SURFACE THROUGH CASING IF M.I.T. TEST PASSED OR WITH TUBING IF M.I.T. TEST FAILED.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2008 10:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,945' & TOPPED WITH 5 SXS. CEMENT. RAN 2 3/8" TUBING INSIDE 5 1/2" CASING & CIRCULATED 55 SXS. CEMENT TO THE SURFACE. TOPPED OFF 5 1/2" CASING WITH 15 SXS. CEMENT. ON 7/9/2008 CHECK TOP PLUG - CEMENT DOWN 26' INSIDE 5 1/2" CASING - NOTIFIED QUALITY TO TOP OFF. 7/10/2008 QUALITY TOPPED OF 5 1/2" CASING WITH 8 SKS. CEMENT. 7/11/2008 CHECK TOP PLUG & CEMENT AT SURFACE. *NOTE: SEE ATTACHED CHRONOLOGY.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY QUALITY OIL WELL CEMENTING, INC. INVOICE #1863.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)