

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20165-00-02
Spot: N2SESE Sec/Twnshp/Rge: 32-2S-23W
810 feet from S Section Line, 660 feet from E Section Line
Lease Name: GRUNERT Well #: 2
County: NORTON Total Vertical Depth: 3602 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1733	0	w/325 sxs cmt
SURF	8.625	283	0	w/180 sxs cmt

Well Type: SWD UIC Docket No: D23708.0 Date/Time to Plug: 06/30/2008 2:30 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 160 sxs 60/40 pozmix - 4% gel - 200# hulls.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2008 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 283' w/180 sxs cement.
4 1/2" production casing set at 1733' w/325 sxs cement.
TD 3602'. PBTD 1733'.
Connected to 4 1/2" casing - pumped 105 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Cement visible in 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
1550	1620		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 10 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #31708 & #31709.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)


CM

Form CP-2/3

JUL 02 2008

PKT

VIKING RESOURCES
 217 E. WILLIAM
 WICHITA, KS. 67202-4005
 CONTR PFEIFER WELL SERVICE, INC. #2 GRUNERT 'OWWO' 32-2-23W
 150'N.
 C SE SE
 CITY NORTON
 FIELD HEN NW
 GEOL _____
 ELV 2306 KB SPD 2/11/85 CARD ISSUED 8/1/85 IP SWDW
 2301 GL DRLG COMP 2/20/85 CED HILLS 1550-1620
 API 15-137-20,165-A



LOG	Tops	Depth/Datum
HEEB	3320-1014
TOR	3348-1042
LANS	3360-1054
BKC	3542-1236
ARB	3573-1267
REAG	3586-1280
GRAN WSH	3593-1287
RTD	3602-1296
LTD	3605-1299

OLD INFO: OPERATOR WAS HUMMON CORPORATION, #2 GRUNERT, SPD 2/6/80, SET 8 5/8 " 283 / 180SX, 4 1/2 " 1733 / 325SX, DRLG COMP 2/20/85, COMP AS SWDW 1586-1624 (CARD ISSUED 8/14/80), CONTR: RED TIGER DRILLING, GEOL: STEVE MILLER
 DST (1) 3373-3405 (LKC) / 30-45-30-60, REC 120' SOCWM, 520' MDY SW, NO PRESSURES RECORDED
 DST (2) 3479-3522 (LKC) / 30-30-30-30, REC 5' DM, SIP 53-53#, FP 43-43#
 MICT - CO, PF (CED HILLS) 1605-1624 & 1586-1605, SWDW - INJECTION RATE SATISFACTORY
 NOTE: INFO RELEASED: WAS OPERATIONS SUSPENDED 4/17/80
 NEW INFO: FR 2/1/85, RE-ENTERED 2/11/85, WSH DWN TO 1675', PROD CSG ALREADY IN HOLE, MICT - CO, PF (CED HILLS) 1550-1620, SWB DWN, SET 2 3/8 " TBG AT 1540', SWDW - INJECTION RATE SATISFACTORY

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS