

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20204-00-00
Spot: S2SESE Sec/Twnshp/Rge: 21-22S-2W
330 feet from S Section Line, 670 feet from E Section Line
Lease Name: WEDEL M Well #: 1
County: HARVEY Total Vertical Depth: 3310 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3303	525	175 SX
SURF	8.625	210		200 SX <u>107.58</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2008 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: SAND TO 3,145' & TOP WITH 4 SXS. CEMENT. RIP 4 1/2" CASING & PULL SAME. RUN TUBING TO 475' & SPOT 35 SXS. CEMENT. PULL TUBING TO 260' & CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/03/2008 2:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 3,141' & TOPPED WITH 4 SXS. CEMENT. RIPPED OFF 4 1/2" CASING @ 525' & PULLED SAME. RAN 2 3/8" TUBING TO 475' & PUMPED 175 SXS. CEMENT. CEMENT DID NOT CIRUCLATE TO SURFACE. PULLED TUBING OUT OF HOLE. WAITED 3 HOURS FOR MORE CEMENT. RAN TUBING TO 210' & TAGGED CEMENT. CIRCULATED 75 SXS. CEMENT TO THE SURFACE. CHECKED TOP PLUG ON 7/7/2008. CEMENT @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
3198	3201		MISSISSIPPISAN

INVOICED
DATE 7-24-08
INV. NO. 2009060138

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE #8204.

Plugged through: TBG

District: 02

Signed

Michael Wilson
(TECHNICIAN)