

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-04878-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 1-20S-2W
1568 feet from S Section Line, 4668 feet from E Section Line
Lease Name: RITZ B Well #: 1
County: MCPHERSON Total Vertical Depth: 2974 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2963	169	
SURF	8.625	140		

96.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2008 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (620) 625-4424

Proposed Plugging Method: HOLE WAS SANDED OFF TO 2,873' & TOPPED WITH 5 SXS. CEMENT. C.I.B.P. SAT AT 800'. WELL PERFORATED FROM 750' & SQUEEED WITH 50 SXS. CEMENT. WELL PERFORATED AT 640' & SQUEEZED WITH 60 SXS. CEMENT. SAND FROM 640 TO 614' & TOP WITH 5 SXS. CEMENT. RIP CASING 2 500' & PULL SAME. RUN TUBING TO 450' & CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/30/2008 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,873' & TOP WITH 5 SXS. CEMENT. SAT C.I.B.P. AT 800'. SANDED FROM 640' TO 614' & TOPPED WITH 5 SXS. CEMENT. RIPPED CASING OFF @ 169'. RAN 1" TUBING IN 8 5/8" X 5 1/2" ANNULUS TO 350' AND HIT CEMENT FROM SQUEEZE AT 640'. RAN 2 7/8 TUBING TO 450' INSIDE 5 1/2" CASING. CIRCULATED 165 SXS. CEMENT FROM 350' INSIDE 8 5/8" X 5 1/2" CASING & FROM 450' IN 5 1/2" CASING TO SURFACE. CHECKED TOP PLUG ON 7/3/08 & CEMENT @ 0'.

Perfs:

INVOICED
DATE 7-24-08
INV. NO. 200 9060138

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32375.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)