

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-01544-00-00

API NUMBER NONE

LEASE NAME Sturgeon

WELL NUMBER 3

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 32 TWP. 9S RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 1-28-56

Plugging Commenced 10-13-92

Plugging Completed 10-13-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P.O. Box 470442, Tulsa, OK 74147

PHONE# (918) 492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on letter dated 9-1-92, Telephone approval 10-1-92, (date)
 by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? yes

Producing Formation Lansing-KC Depth to Top 3620' Bottom 3644' T.D. 3883'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing-KC	Oil	0'	238'	8 5/8"	238'	
		0'	3883'	5 1/2"	3883'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled casing and formation void with 375 sx. 60-40-pozmix 10% gel, 1 sx. cello flake, 7 sx. of hulls, Pumped cement to maximum 400#. Standing pressure 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Robert R. Price Operating, Inc. License No. 6273

Address P.O. Box 470442, Tulsa, OK 74147

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert R. Price Operating, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price (Employer, Agent, Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert R. Price
 (Address) P.O. Box 470442, Tulsa, Oklahoma 74147

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1992

Rachel Shanks Notary Public

My Commission Expires: February 26, 1994



Sunray, Mid-Continent Oil Co.
Tulsa, Oklahoma

Tulsa, Oklahoma
January 31, 1956

CONTRACTOR: Stickle Drilling Company
DRILLING COMMENCED: January 18, 1956
DRILLING COMPLETED: January 28, 1956

Sturgeon #3 - NE/4 of Sec.
32-9S-22W, Graham County,
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Shale & Sand	660
Shale, Shells & Sand	1295
Sand & Shale	1695
Shale & Shells	1915
Anhydrite	1940
Shale Red Bed & Shells	2275
Shale & Lime	3600
Lime & Shale	3662
Lime	3885 TD

I, Frank E. Stickle hereby certify the above to be a true and complete
Drillers Log of Sunray Mid-Continent Oil Company's Sturgeon #3, NE/4 of
Section 32-9S-22W, Graham County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My Commission Expires

RECEIVED
STATE COMMISSION

AUG 27 1992

CONSERVATION DIVISION
Wichita, Kansas