

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 32 TWP. 9 RGE. 22W E/W
Location as in quarters or footage from lines:
C S/2 NE SE

Lease Owner Arrowhead Petroleum, Inc.
Lease Name Jeffers A-1 Well No. _____
Office Address Suite 29 400 N. Woodlawn Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 7-13-82
Plugging completed 7-19-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom T.D. 3871'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	216'	none
				4-1/2"	3870'	3003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand and 4 sacks cement and pushed bottom plug to 3750'. Shot casing @3190', and 3027'. Pulled a total of 73 joints of 4-1/2" casing. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 6% gel, 3% cc.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION

8/2/82
AUG 02 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 82



Irene Hoover
Notary Public.

My Commission expires: _____