


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM County. Sec. 35 Twp. 9S Rge. 22W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SE SE
Lease Owner K & E DRILLING, INC.
Lease Name MOORE 'C' Well No. 1
Office Address 719 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-7-58 19
Application for plugging filed 1-7-58 19
Application for plugging approved 1-7-58 19
Plugging commenced 1-7-58 19
Plugging completed 1-7-58 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	232'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with heavy mud to 700', set wood plug with 25 sx cement thru drill pipe. Fill with heavy mud to 210', set wood plug with 15 sx cement thru drill pipe. Fill with heavy mud to 40', set plug with 10 sx cement to base of cellar. Job Complete
1-7-58


RECEIVED
STATE CORPORATION COMMISSION
1/17/58
JAN 17 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 16th day of January, 19 58
Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC 35 T 9 R 224
BOOK PAGE 75 LINE 13

W E L L L O G

OPERATOR:	K & E DRILLING, INC. 719 Union Center Building Wichita, Kansas	FARM NAME:	#1 MOORE 'C'
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Building Wichita, Kansas	LOCATION:	SW SE SE Sec. 35-98-22W Graham Co, Kansas
CASING:	8-5/8" @ 232' (160 sx)	COMMENCED:	1-1-58
R.T.D.	3810'	COMPLETED:	1-7-58
		PRODUCTION:	D & A
		ELEVATION:	2312' KB

FORMATION RECORD

Cellar	8
Clay & Soil	20
Sand	40
Shale	231
Shale & Shells	1220
Sand & Shale	1520
Red Bed & Shale	1780
Anhydrite	1825
Shale & Shells	2200
Shale & Lime	2915
Lime & Shale	3350
Lime	3455
Lime & Shale	3547
Lime	3810
R.T.D.	3810

STATE CORPORATION COMMISSION

JAN 17 1958

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the #1 Moore 'C' well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 16th day of January, 1958.

Patricia M. Edwards
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING
1958 ST. 2 R 224
PAGE 75 LINE 43