

15-065-21029-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 35 Twp. 9S Rge. 22W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW NW


Lease Owner Tomlinson Oil Company
Lease Name D. E. Tremblay Well No. 1
Office Address 200 W. Douglas, Ste. 700, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed Feb. 17 19 79
Application for plugging filed (verbally) Feb. 17 19 79
Application for plugging approved (verbally) Feb. 17 19 79
Plugging commenced Feb. 17 19 79
Plugging completed Feb. 17 19 79

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4007'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4007'
Set 1st plug at 900' with 70 sacks
2nd plug at 200' with 20 sacks
3rd plug at 40' with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 9:30 a.m., 2-17-79.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.



(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 79

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: D. E. Tremblay #1
 LOCATION: SE SW NW, Section 35-9S-22W
 Graham County, Kansas
 SPUD DATE: February 09, 1979
 COMPLETION DATE: February 17, 1979

0	247	Sand and shale
247	1432	Sand and shale
1432	1510	Sand
1510	1829	Shale
1829	1867	Anhydrite
1867	2450	Shale
2450	3085	Shale and lime
3085	4007	Lime and shale
	4007	Rotary Total Depth

SAMPLE TOPS:

Anhydrite 1829'
 B/Anhydrite 1867'

Spud hole at 7:30 p.m., February 9, 1979. Drilled 247' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# used casing. Set at 245.47' K.B. with 175 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 11:45 p.m., February 9, 1979.

T.D. 4007'. Set 1st plug at 900' with 70 sacks, 2nd plug at 200' with 20 sacks, 3rd plug at 40' with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:30 a.m., February 17, 1979.

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


RECEIVED
 STATE CORPORATION COMMISSION
 FEB 26 1979
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the D. E. Tremblay #1, SE SW NW, Section 35-9S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 23rd day of February, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.