


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 35 Twp. 9 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines S/2 SE/4
Lease Owner ~~XXXXXX~~ Leslie Oil Company
Lease Name Moore "A" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-18-62 _____ 19____
Plugging completed 5-21-62 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3933 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None
				5-1/2"	3920'	1196'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3933', sanded to 3900' and dumped 4 sacks of cement @ 3900' with dump bailer. Pulled 22 jts. of 5 1/2" casing and pumped in 23 sacks of gel mud. Pulled 1 jt. of 5 1/2" casing and circulated with 2 more sacks of gel mud. Pumped in 20 sacks of cement @ 400', pulled 5 1/2" casing to 180' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed mud to 35' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
5/31/62
MAY 31 1962
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or XXXXXX (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1962

My commission expires May 20, 1964 Milton J. Volin Notary Public.

15-265-03021-00-00

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
April 23, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: April 10, 1957
Drilling Completed: April 19, 1957

M. Moore "A" #1 S/2
SE/4 Sec. 35-9S-22W,
Graham County, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1962

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Depth figures indicate base of formation:

Sandy Red Bed	40
Sand & Shale	245
Shale	1207
Shale & Shells	1800
Anhydrite	1824
Shale & Shells	2315
Shale & Lime	2660
Lime & Shale	2805
Shale & Lime	3405
Lime & Shale	3568
Lime	3754
Lime & Shale	3929
Arbuckle	3933 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's M. Moore "A" #1 S/2 SE/4 Section 35-9S-22W, Graham County, Kansas.

Frank E. Stickle
Frank E. Stickle

William T. Bonham
Notary Public

February 13, 1960
My Commission expires