

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

22558

API NUMBER 15-065-23,558-00-00

LEASE NAME Tremblay KCC  
Tremblay CAW

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4940 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 35 TWP. 9S RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 3/31/90

Plugging Commenced 3/31/90

Plugging Completed 3/31/90

LEASE OPERATOR Howard O. Williford

ADDRESS RR #1, Box 35, Alsen, KS 67512

PHONE#(316) -278-3195 OPERATORS LICENSE NO. 30326

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 31, 1990 (date)

by Herb Dinnes (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	215'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4000'-3970' 40 sks cement @ 265'

25 sks cement @ 3970' 10 sks cement @ 40'

25 sks cement @ 1860' 15 sks in rathole

100 sks cement @ 1110'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Howard O. Williford

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
4/3/90  
10 3 1990

(Signature) [Signature]

Kyle B. Branum

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 90

GLEND A. R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

[Signature]  
Glenda R. Tiffin, Notary Public

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Howard O. Williford  
RR #1, Box 35  
Alden, KS 67512

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Tromblay WELL #1

LOCATION: 10' South of NW NE NW  
Section 35-9S-22W  
Graham County, Kansas

LOGGERS TOTAL DEPTH: 3999'

ROTARY TOTAL DEPTH: 4000'

COMMENCED: 3/23/90

CASING: 8-5/8" @ 215' w/140 sks cement

ELEVATION: 2365' K.B.

COMPLETED: 3/31/90

STATUS: Dry Hole

DEPTHS & FORMATIONS


(All measurements from K.B.)

Top Soil & Sand	60'	Lansing-Kansas City	3585'
Dakota Sand	1103'	Base Kansas City	3814'
Cedar Hills	1359'	Marmaton	3878'
Anhydrite	1840'	Arbuckle	3981'
Heebner	3548'	R.T.D.	4000'
Toronto	3569'		

STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above-captioned well, to the best of his knowledge.


RECEIVED  
STATE CORPORATION COMMISSION  
APR 03 1990  
ELEVATION DIVISION  
Kansas  
Wichita

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on April 2, 1990.

My commission expires: February 6, 1992.

  
GLEND A. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

  
\_\_\_\_\_  
Glenda R. Tiffin, Notary Public