

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19035-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 21-14S-19W
321 feet from S Section Line, 2307 feet from E Section Line
Lease Name: KRAUS (SOUTH) Well #: 5
County: ELLIS Total Vertical Depth: 3880 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3811	0	w/398 sxs cmt
SURF	8.625	214	0	w/125 sxs cmt <u>126.10</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2008 9:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Emergency plug with rig over the hole.
Tubing and packer in the hole at 1512'. Casing parted.
CIBP at 3410' with 2 sxs sand over plug.
1750' - 1790' squeeze with 300 sxs.
Operator elected all cement plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2008 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1500'. Swift rigged to tubing - pumped 170 sxs 60/40 pozmix - 4% gel to circulated cement out of 5 1/2" casing and 8 5/8" casing.
Pulled tubing - rigged to 5 1/2" casing with a swedge - shut in 8 5/8" casing - pumped 30 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3800	3804		

INVOICED
DATE 8-18-08
INV. NO. 2009060245


RECEIVED
KANSAS CORPORATION COMMISSION
AUG 07 2008

Remarks: SWIFT SERVICES, INC.-TICKET #13821.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

AUG 04 2008