

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24272-00-00
Spot: NWSENV Sec/Twnshp/Rge: 23-15S-18W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WERTH Well #: 2
County: ELLIS Total Vertical Depth: 3857 feet

Operator License No.: 31225
Op Name: HADDOCK, JACK L.
Address: 778 TOULON AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3815	0	w/50 sxs cmt
SURF	8.625	218	0	w/150 sxs cmt

125.35

Well Type: SWD UIC Docket No: D24149.0 Date/Time to Plug: 07/31/2008 3:00 PM
Plug Co. License No.: 31225 Plug Co. Name: HADDOCK, JACK L.
Proposal Rcvd. from: EUGENE LEIKER Company: HADDOCK, JACK L. Phone: (785) 628-3628

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.
DV at 1190' cwc w/325 sxs cement.
Junk in the hole. Well was flowing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2008 6:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1000'. Allied rigged to tubing - pumped 65 sxs 60/40 pozmix 4% gel to circulate cement to surface.
Pulled tubing. Allied rigged to 4 1/2" casing with a swedge - pumped 130 sxs cement with 200# hulls mixed in.
Max. P.S.I. 1200#. S.I.P. 800#.
Rigged to 8 5/8" casing - pumped 20 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3815	3857	OH	

INVOICED
DATE 8-18-08
INV. NO. 2009060247

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 07 2008


CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #31780.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

PP

EDWARD P. LEIKER

HC32, BOX 132

HAYS, KS. 67601

#2 WERTH

23-15-18W


NW SE NW

CONTR RED TIGER DRILLING

CTY ELLIS

GEOL EDWARD P. LEIKER

FIELD LEIKER SE



ELV 1983 KB SPD 7/13/85

CARD ISSUED

9/12/85

IP SWDW

1978 GL

DRLG COMP 7/19/85

GRAN OH 3815-3857

SMP	Tops	Depth/Bottom	
			API 15-051-24,272
			8 5/8 " 200 /150SX, 4 1/2 " 3815 /375SX
			NO CORES OR DST'S
			MICT - CO, (GRAN OH), SWB DWN, SWDW - INJECTION RATE
			SATISFACTORY
HEEB		3228-1243	
KC		3274-1291	
CONG		3565-1582	
ARB		3590-1607	
REAG SD		3760-1777	
GRAN		3820-1837	
RTD		3857-1874	

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS