

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22405-00-00
Spot: N2NWSESE Sec/Twnshp/Rge: 31-19S-10W
1170 feet from S Section Line, 990 feet from E Section Line
Lease Name: BAYER Well #: 1
County: RICE Total Vertical Depth: 3294 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|----------------------|
| PROD | 5.5 | 3293 | | 140 SX |
| SURF | 8.625 | 238 | | 225 SX <u>107.06</u> |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2008 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO / DENNIS HU Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/23/2008 4:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OFF ARBUCKLE AND CAP WITH 5 SX'S CEMENT, SET BRIDGE PLUG @ 2750' AND CAP WITH 2 SX'S CEMENT. CUT OFF CASING @ 1900' AND PULL TO 1300', ESTABLISH CIRCULATION AND PUMP 35 SKS CEMENT, PULL CASING TO 900' AND PUMP 35 SX'S CEMENT, PULL CASING TO 288' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3293 | 3294 | | ARBUCKLE |
| 3194 | 3204 | | LANSING |
| 3110 | 3114 | | LANSING |
| 3026 | 3030 | | LANSING |
| 2924 | 2938 | | DOUGLAS |
| 2794 | 2800 | | TOPEKA |

INVOICED

DATE 8-18-06
INV. NO. 2009060249

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #35378. LOG TECH #5398

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PK