

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23750-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 25-9S-18W
1000 feet from S Section Line, 1800 feet from E Section Line
Lease Name: DEVENY Well #: 3
County: ROOKS Total Vertical Depth: 3678 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		

119.54

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/30/2008 8:00 AM
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC
Proposal Rcvd. from: BOB MICKELSON Company: LIBERTY OPER & COMPL, INC. Phone: (620) 388-3818

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: PARTIAL
Date/Time Plugging Completed: 07/30/2008 9:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3603' w/25 sxs.
2nd. Plug at 1475' w/25 sxs.
3rd. Plug at 907' w/100 sxs. (3rd Plug to Rathole witnessed by Rich Williams)
4th. Plug at 267' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 25 sxs.

Perfs:

INVOICED

DATE 8-18-08
INV. NO. 2009060252

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

Form CP-2/3

JUL 31 2008

PKT