

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23197-00-00
Spot: NENWSW Sec/Twnshp/Rge: 23-27S-21E
2495 feet from S Section Line, 1060 feet from W Section Line
Lease Name: INMAN Well #: A3-23
County: BOURBON Total Vertical Depth: 862 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	854	0	95 SX CMT.
SURF	8.625	21	0	4 SX CMT.
T1	2.375	418	0	

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/10/2008 1:30 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 854' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 2:15 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FRIST OF THE CEMENT TO BE PUMED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400 PSI. 71 SAACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
385	389		
374	377		

RECEIVED
KCC DISTRICT #3

JUL 30 2008

CHANUTE, KS

INVOICED

DATE 8-18-08

INV. NO. 2009060254

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PKT