

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-26269-00-00
Spot: S2NESENE Sec/Twnshp/Rge: 22-27S-21E
1833 feet from N Section Line, 352 feet from E Section Line
Lease Name: INMAN Well #: 22-2D
County: NEOSHO Total Vertical Depth: 856 feet

Operator License No.: 33504
Op Name: PAXTON JACKSON, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	854	0	
SURF	8.625	21	0	4 SX CMT 35
T1	2.375	830		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 07/10/2008 11:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 854' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 400 PSI.. 77 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
754	756		
700	702		
694	696		
555	557		
519	521		
479	481		
450	452		
365	368		
354	357		

RECEIVED
KCC DISTRICT #3

JUL 30 2008 CRT

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

INVOICED

DATE 8-18-08
INV. NO. 2009060254

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKS