

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-26292-00-00
Spot: S2NENWNE Sec/Twnshp/Rge: 22-27S-21E
355 feet from N Section Line, 1650 feet from E Section Line
Lease Name: INMAN Well #: C 1-22
County: NEOSHO Total Vertical Depth: 836 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	818		95 SX CMT
SURF	8.625	21		4 SX CMT

35

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 07/09/2008 12:30 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (624) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 818' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/09/2008 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FRIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSRUE. THE WELL WAS THEN SHUT IN AT 500P.S.I. 70 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3
JUL 30 2008 CRT
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
662	666	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 04 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

INVOICED
DATE 8-18-08
INV. NO. 2009060254

District: 03

Signed Clayton P. Titel
(TECHNICIAN)