

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-26293-00-00
Spot: NESWNE Sec/Twnshp/Rge: 22-27S-21E
1680 feet from N Section Line, 1712 feet from E Section Line
Lease Name: INMAN Well #: C 2-22
County: NEOSHO Total Vertical Depth: 826 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	809		95 SX CMT
SURF	8.625	22		4 SX CMT 35

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/09/2008 2:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 809' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/09/2008 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THTE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTONSEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600PSI. 72 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
732	738	CSG	

INVOICED
DATE 8-18-08
INV. NO. 2009060254

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 04 2008
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #3
JUL 30 2008
CHANUTE, KS

CPT

Remarks:
Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

Handwritten initials