

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-26294-00-00
Spot: NENWSE Sec/Twnshp/Rge: 22-27S-21E
2282 feet from S Section Line, 1705 feet from E Section Line
Lease Name: INMAN Well #: C 3-22
County: NEOSHO Total Vertical Depth: 862 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	844		95 SX CMT
SURF	8.625	21		4 SX CMT

35-

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/10/2008 9:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: _____ Company: W & W PRODUCTION COMPANY, Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 844' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/10/2008 10:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 500 PSI.. 71 SACKS OF CEMENT WERE PUMPE INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
762	765	CSG	
707	709	CSG	
700	702	CSG	
480	482	CSG	
365	369	CSG	
354	357	CSG	

RECEIVED
KCC DISTRICT #3

JUL 30 2008

CHANUTE, KS

CPT

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

INVOICED

DATE 8-18-08
INV. NO. 2009060254

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PPT