

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-26299-00-00  
Spot: S2NENESE Sec/Twnshp/Rge: 22-27S-21E  
2251 feet from S Section Line, 332 feet from E Section Line  
Lease Name: INMAN Well #: D 3-22  
County: NEOSHO Total Vertical Depth: 858 feet

Operator License No.: 33503  
Op Name: PAXTON GRANT, LLC  
Address: 132 N OTSEGO AVE  
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	840		95 SX CMT
SURF	8.625	22		4 SX CMT <u>35-</u>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2008 3:00 PM  
Plug Co. License No.: 5490 Plug Co. Name: WIMSETT OIL, INC.  
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 840' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 07/10/2008 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 650 PSI. 70 SACKS OF CEMENT WERE PUMPED INTO THIS WELL,

Perfs:

Top	Bot	Thru	Comments
749	752	CSG	
696	698	CSG	
689	691	CSG	
501	504	CSG	
477	479	CSG	
365	3369	CSG	
354	357	CSG	

RECEIVED  
KCC DISTRICT #3  
JUL 30 2008 CPT  
CHANUTE, KS

INVOICED

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 04 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \_\_\_\_\_  
Plugged through: CSG  
DATE 8-18-08  
INV. NO. 2009060254

District: 03 Signed Clayton P. Titel  
(TECHNICIAN)

PPT